



VORTEX

ENGINEERING SERVICES

Automation, Control & Maintenance,
Electrical & Mechanical Engineering Services

QUOTE

M/S: GUL AHMED TEXTILE MILLS
ATTN: M SAMI

QUOTE: 0000000004

Date: 04-Dec-2021

VALIDITY: 07 days

Subject: QUOTATION FOR SUPPLY OF PANEL DB

PANEL DB

QTY-01

S#	DESCRIPTIION	RATING	QTY	MODEL
INCOMING				
1	160A	25KA	1	ABB
1	3A SP FOR CONTROL	4.5KA	3	CHINT
1	PAHSE INDICATION LIGHT	200VAC	3	YUMO/CAMSCO
OUTGOING				
1	63A TP MCCB	16KA	2	TERASAKI
1	32A TP MCCB	16KA	3	TERASAKI
1	20A SP MCB	6KA	6	TERASAKI
1	10A SP MCB	6KA	6	TERASAKI
PANEL DB WITH RAL 7035 POWDER PAINT, COMPONENT, COPPER, WIRING & MATERIAL				
AMOUNT		Rs. 88,500		
DISCOUNTED AMOUNT		Rs. 63,500		

Payment: 75% payment in advance along with firm order, balance payment after completion job before delivery.

Tax: Our quoted prices are exclusive of all taxes. GST @ 22% to be added.

Cartage: Please include transportation charges.

Extra: Any Item, material, labour exceeding above quantities will be charged additionally.

Delivery: Delivery within 6 - 8 Weeks after receipt of firm order.

Validity: This offer is valid for 07 days from the date of this letter.

Note: Please note that due to pandemic situation in market, the availability of material may cause some delay, we will try our best to habdel with the situation for timely delivery of material.

Yours Sincerely,
For Vortex Engineering Services